

What it Costs (<https://www.homepowersystems.net/resources/what-it-costs/>)

Below are Generator and Installation Benchmark Costs:
(Total Turn-Key Solution Including Generator)

WHOLE HOUSE TRANSFER - GENERAC AIR COOLED GENERATORS

MODEL NO.	SIZE	RATED CONTINUOUS POWER CAPACITY (NG)	RATED LOAD CURRENT 240V 1 PHASE (NG)	MAIN BREAKER RATING	TURN-KEY INSTALL PRICE RANGE (LP-NG)	TYPE OF SE RATED SWITCH INCLUDED IN QUOTE
7037	16kw	16,000 watts	66 amps	70 amp	\$9,000.00 – \$10,700.00	RTS-W-200A3
7039	20kw	18,000 watts	75 amps	90 amp	\$9,700.00 – \$11,500.00	RTS-W-200A3
7043	22kw	19,500 watts	86.3 amps	100 amp	\$10,000.00 – \$11,700.00	RTS-W-200A3

PACKAGED SELECTED CIRCUIT GENERAC AIR COOLED GENERATORS

MODEL NO.	SIZE	RATED CONTINUOUS POWER CAPACITY (NG)	RATED LOAD CURRENT 240V 1 PHASE (NG)	MAIN BREAKER RATING	TURN-KEY INSTALL PRICE RANGE (LP-NG)	TRANSFER SWITCH CIRCUITS
7030	9kw	8,000 watts	33.3 amps	35 amp	\$6,600.00 – \$8,800.00	10
7032	11kw	10,000 watts	42 amps	50 amp	\$7,100.00 – \$8,800.00	12
7036	16kw	16,000 watts	66 amps	70 amp	\$9,000.00 – \$10,400.00	16

GENERAC LIQUID COOLED GENERATORS 1 PHASE 120/240V

ELITE MODEL NO.	SIZE	RATED CONTINUOUS POWER CAPACITY (NG)	RATED LOAD CURRENT 240V 1 PHASE (NG)	MAIN BREAKER RATING	TURN-KEY INSTALL PRICE RANGE	INCLUDES 200AMP TRANSFER SWITCH #RTS-W-200A3
RTG02224	22kw	22,000 watts	91.6 amps	100 amp	Call for Quote	Yes
RTG02724	27kw	27,000 watts	112.5 amps	125 amp	Call for Quote	yes
RG03224	32kw	32,000 watts	133 amps	150 amp	Call for Quote	yes
RTG03824	38kw	38,000 watts	158 amps	175 amp	Call for Quote	yes
RTG04854	48kw	48,000 watts	200 amps	200 amp	Call for Quote	yes

Pricing Notes *

All above "Total Turn-Key Solution" is for work installed by Home Power Systems in Rochester and Syracuse, New York only. Other Generac Dealer prices may be different.

Pricing includes:

- One-Day Installation
- Town permitting – A permit is required in most towns.
- Electrical inspection by Independent Electrical Inspection Agency.
- A generator sized to meet your expressed requirements. HPS is an authorized Generac PowerPro Premier Dealer and warranty repair company.
- Professional transport, rigging and handling of each generator to your home.
- Electrical installation completed per latest local and national building codes.
- Coordination with local gas utility in completing Gas Inventory Report for gas meter upgrade, if required (Separate utility upgrade costs may be required to support generator).
- Includes updating grounding of homes electrical service per new NEC, article 250 codes.
- Mechanical natural gas raceway installed by an experienced mechanic and per manufacturer's installation guidelines and New York State Gas Codes. This includes 1" minimum gas raceway to the generator.
- Battery sized per manufacturer's recommendations.
- Basic generator site prep including the installation of pea gravel base per manufacturer's recommendations.
- On-site manufacturer recommended commissioning and startup of the generator. Obtain startup activation code from the factory. Adjust frequency and calibrate voltage output, exercise transfer switch and balance loads for a complete and functional system. Includes setting exercise time & owner training.
- 20 – item Customer Final Approval Checklist.
- Operation & Maintenance manual in 3-ring binder.
- 2-year maintenance program as called out in section 4 (1 visit per year).
- 2-year warranty covering all parts and labor on the generator. Being a Generac PowerPro Premier there will be no issues if a warranty issue comes up.
- 24/7 Emergency service with repairs by factory trained technicians in fully stocked vans.